



January 17, 2025

ADDENDUM NO. 2

RETAINING WALL RECONSTRUCTION AT BRYAN BELT LINE ROAD

BID NO. 2025-013

Bidders are directed to revise and incorporate into their bid the following change(s) in bid specifications:

QUESTIONS AND ANSWERS:

Question 1: How to construct the retaining wall at storm inlets?

Response: The retaining wall will be constructed following the TXDOT Retaining Wall Detail RW(SFC). Similar to the as-built drawings for retaining wall footings at inlets, the proposed wall footing will be cast against the inlet box with ½-inch expansion joints. As a result, the wall will be bumped out at the inlet locations. For a 5-foot wall (4 feet measured from the surface of the adjacent sidewalk to the top of the wall), the width of the footing (Hw) is 3 feet.

Question 2: Do we have as-build drawings for the ROW and existing retaining walls?

Response: Yes, the drawings are attached. Please note that the existing retaining walls were not built 100% per the plan.

Question 3: Does city require flex base below the sidewalk?

Response: Flex base material is required only when it is necessary to bring the sidewalk to grade. In this project, the flex base will be included as part of the sidewalk item and will not be paid for separately.

CHANGES TO BID ITEMS:

1. Modified item 7 and added a new item. (See revised Bid Proposal attached)

AS-BUILD DRAWINGS:

2. As-build drawings for the existing tanks are included in this addendum.

If you should have any other questions, do not hesitate to contact the Purchasing Office at 972-216-6201.

Ryan Williams

Ryan Williams

Manager of Purchasing

ACCEPTANCE:

We, the undersigned, do hereby acknowledge receipt of this Addendum No. 2 to Bid No. 2025-013: Retaining Wall Reconstruction at Bryan Belt Line Road and agree to the instructions herein written.

Company Name

Authorized Signature

Date

**RETAINING WALL RECONSTRUCTION AT BRYAN-BELT LINE ROAD
CITY OF MESQUITE CONTRACT NO. 2025-013**

MESQUITE, TEXAS

ITEM NO	ITEM DESCRIPTION	UNITS	BID QUANTITIES	UNIT PRICE	AMOUNT
1	Mobilization	LS	1		
2	Traffic control implementation and maintenance	LS	1		
3	Implementation of erosion control devices	LS	1		
4	Remove existing retaining wall, excavate to obtain working space, and construct approximately 145 LF of a 4-foot-tall (measured from surface of the adjacent sidewalk) spread footing retaining wall in accordance with TXDOT specifications	LS	1		
5	Retaining wall backfill, compact, and sod to match existing turf	LS	1		
6	Remove and replace 4-inch concrete sidewalk associated with the retaining wall (optional)	LS	1		
7	Construct 4-inch concrete sidewalk, 5-ft in width	LF	340		
8	Construct 4-inch concrete sidewalk with 6-in to 12-in retaining wall per City Detail P-15, 5-ft in width	LF	290		
9	Construct ADA ramp, Type D	EA	4		
10	Reconstruct existing inlet top (optional)	EA	4		
11	Install sod to match the existing turf, excluding the area behind the retaining wall	SY	200		
12	Irrigation system repair allowance	AL	-	\$ 2,500.00	\$ 2,500.00

TOTAL BASE BID (Items 1 to 11)

\$ _____

1. Materials incorporated into the Project:

\$ _____

2. All other charges:

\$ _____

NOTE: Materials and all other charges incorporated into the **RETAINING WALL RECONSTRUCTION AT BRYAN-BELT LINE ROAD, CITY OF MESQUITE CONTRACT NO. 2025-013** must equal base bid amount.